

1996-2003

<p>BG EXPLORATION AND PRODUCTION INDIA LTD</p>	<p>Replacement of corroded/damaged piggy clamp 10 nos. on Riser MTA, 06 nos. on Riser STC and 0 nos. on Riser STA. Installation of continuity cable for C.P. improvement on all three Riser Piggy Back clamp line. Installation of 1000 kg riser clamps on bottom most location on Riser STC.</p> <p>Installation of 750 kg anode clamp on MB16 and injection grouting inside the member. Scour reading of all six leg and Post C.P. reading of all installed clamp.</p> <p>Installation of barge bumper securing chains and C.P. improvement. Above job carried out in TAPTI field in almost nil visibility water and peak current was 7 knots.</p>	<p>TAPTI</p>	<p>May 2003</p>
<p>DAS OFFSHORE ENGG. PVT. LTD.</p>	<p>Underwater installed 20 nos. of bracelet anodes on PD Platform, C.P. Reading and Video graphy carried out of all installed anodes under DNV Supervision, Installed 4 nos. Barge Bumper on PB, PG, PC and MA platform.</p>	<p>PMT FIELD.</p>	<p>MAR, MAY 2001</p>
<p>M/S. MAZAGON DOCK LTD., MUMBAI.</p>	<p>Replacement of fasteners (Nut Bolt) on "SR" Platform total 98 no. fasteners changed. Tightened continuity bolt and Videography of all changed fastener, tightened continuity bolts and Videography of all changed fasteners continuity bolts.</p>		<p>Feb 1998</p>
	<p>Underwater Cathodic protection survey (C.P. Survey) of jacket B-55 & B-121 at various level and member as per scope of work. Air & gas diving carried up to EL - -70.00 meter</p>		<p>April 1998</p>
	<p>Underwater survey of firewater pump caisson from surface to bottom of strainer underwater Videography of firewater pump caisson on NA and SA platform.</p>		<p>Mar-Apr 2000</p>
	<p>Underwater Pre-engineering survey of B-1 leg for fitment of sump caisson clamp from EL -00 meter. To EL -60mtr. And underwater video survey of obstructions on B-1 leg BHN (NF) platform.</p>	<p>MUMBAI HIGH</p>	<p>Mar 2000</p>

M/S. MAZAGON DOCK LTD., MUMBAI.	Underwater Replacement of 24 in nos. fasteners at EL -57.00mtr. On conductor clamp on SM platform. Pre & Post video survey carried out Tightening of 4 in nos. continuity bolt		Mar 2000
	Underwater cutting of strainer grating on firewater pump caisson for installation of new strainer and re-fixing of grating by using bolting system on NA platform. Underwater video survey of post installation of strainer.		Apr 2000
	Underwater survey and cleaning of Marine growth up to EL-60mtr. Level and removing and cutting obstructions for installation of sump caisson and clamps on B-1leg BHN (NF) platform.	MUMBAI HIGH	Apr 2000
	Underwater Installation of 72mtr. Long, 2mtr. Dia of Sump Caisson with 4 clamps of 7 ton each at elevation -5.5mtr., -19.5mtr., -34mtr., -50mtr. At B1 leg of BHF platform (BHN) and installation of 8nos. bracelet anodes and relocation of 3nos. jacket anode. Installation of Rigid fender on B1-leg.	MUMBAI HIGH	Dec 2000 to Mar 2001
	Installation of 2 nos. Buoys for the Jacket Load out on Barge in position for HV Project. Removal of 2 nos. Buoys after completion of Load out		2-Mar-2000
Leighton contractors (India) pvt. Ltd	Air diving support for "G1 & GS15 field development shallow water works for Pre Engineering Monopod Survey, Installation of Risers, Y Joint, Post Trenching, Metrology and Installation of Spool	KAKINADA	9 th May 2011
M/S. Buda B.V. Dredging & Contractor	Underwater pipeline support and concrete mat placing on pipeline.		Mar - April 1998
M/s. Hyundai Heavy Industries Co. Ltd.	Underwater Pre-Engineering & video survey of 7 jacket of existing Riser 'HV' Project of ONGC	HEERA & NEELAM	1 st Nov
M/s. Enron Offshore Power Operation C.V, (Dabhol)	Underwater diving work on SBM for survey of SBM chain	Enron, Dabhol	1 st Apr
Jawaharlal Nehru Port Trust	Shifting of Navigational Buoy in JNPT Channel		5 th Dec
Shipping Corporation of India	Installation of D-Shackles and Chains for SBM & SPM at ONGC supply base,	MUMBAI PORT	4 th Apr